

Scheduled Asbestos Abatements

Nettie E Karcher School
225 Robert Street
Burlington, WI 53105

Asbestos Abatement in Classrooms 29 & 32
Date: June – July 2011

- Remove approximately 42 linear feet of friable asbestos containing thermal pipe insulation.
- Remove approximately 29 friable asbestos containing thermal pipe fittings in room 29.
- Remove approximately 2, 208 square feet of non-friable Category I asbestos containing floor tile and black mastic in room 29.
- Remove approximately 300 square feet of drywall walls and associated friable asbestos containing drywall joint compound in room 32.
- Remove approximately 300 square feet of non-friable Category I asbestos containing floor tile on wood.

Waller Elementary School
195 Gardner Ave.
Burlington, WI 53105

Asbestos Abatement in Classrooms 210,212,214,216,218,225,227,229,231,233,235,
kitchen & north mechanical room.
Date: June – July 2011

- Remove approximately 8,275 square feet of non-friable Category I asbestos containing floor tile and black mastic in classrooms.
- Remove approximately 796 square feet of non-friable Category I asbestos containing floor tile and black mastic in kitchen.
- Remove approximately 64 square feet of non-friable Category I asbestos containing floor tile and black mastic in north mechanical room.
- Remove approximately 24 friable asbestos containing thermal pipe fittings and associated fiberglass insulation via glovebag method.